

NSLS-II Accelerator Overview & Lessons Learned



Bill Wahl
Accelerator Division Injector Engineer, BNL NSLS-II
DLSR Workshop
November 19-21, 2014

Outline

- Design features & project scope
- Phasing of installation
- Production and installation approach
- Review of accelerator installation (Injector & Storage Ring)
- Readiness and commissioning achievements
- Project performance
- Critical Paths identified
- Lessons learned
- Labor profile
- Challenges

NSLS-II Design Features

Highly optimized x-ray synchrotron delivering:

- Extremely high brightness and flux
- Exceptional beam stability
- Advanced instruments, optics, and detectors


Design Parameters

- 3 GeV, 500 mA, top-off injection system
- Circumference 792 m
- 30 Cell, Double Bend Achromat Lattice
 - 15 high-beta straights (9.3 m)
 - 15 low-beta straights (6.6 m)

Novel design features:

- Damping wigglers
- Large gap IR dipoles
- Soft bend magnets
- Long beamlines
- Three pole wigglers
- Ultra-high stability

Ultra-low emittance for high brightness and small source size



NSLS-II Project Scope

Accelerator Systems

- Storage Ring – 792m circumference
- Top-Off Injection System

Conventional Facilities

- Ring Building and Service Bldgs (400,000 gsf)
- 5 Laboratory/Office Bldgs (190,000 gsf)


Experimental Facilities

- Capable of hosting at least 58 beamlines


Research & Development

- Advanced optics & accelerator components
- Initial suite of 8 beamlines (two canted)
(XPD, SRX, CSX, HXN, CHX & IXS)

Total Project Cost \$912M (Baseline)



Phasing of Construction and Installation



Beneficial Occupancy		
Area	Original Date	Actual Date
Pentant 1 (P1)	1-Feb-11	14-Mar-11
RF Bldg. (RF)	23-Mar-11	16-Jun-11
Booster (BR)	18-May-11	12-Aug-11
Linac (LN)	18-May-11	12-Aug-11
Pentant 2 (P2)	2-Jun-11	21-July-11
Pentant 3 (P3)	27-Sep-11	21-Oct-11
Pentant 4 (P4)	28-Nov-11	21-Dec-11
Pentant 5 (P5)	9-Feb-12	29-Feb-12

- Received building in stages; temporary walls constructed
- Installation started as soon as Beneficial Occupancy was received (starting with Pentant 1 in March of 2011)
- LOB 1,3 & 5 - fully built and occupied
- LOB 4 - 50% complete/occupied
(balance to be completed in the spring of 2015)
- LOB 2 - Shell is complete (currently used for storage)

Building Construction



Production and Installation Approach

Accelerator Production

- BNL procured Injector sub-systems (Linac, Booster Ring)
- BNL built and integrated Transfer Lines, Booster RF and SR components

Accelerator Installation

- | | |
|-------------------|--|
| • Linac | Vendor w/ BNL oversight |
| • Booster Ring | Vendor using BNL technicians for all hands-on work w/ vendor oversight |
| • Booster RF | BNL |
| • Transport Lines | BNL |
| • Storage Ring | BNL |
| • Storage Ring RF | Combination of BNL & Vendors |

Injector

Linac

- 90 keV electron gun
- Four accelerator sections that accelerate electron beam to 200 MeV before it reaches the LtB Transport Line

LtB Transport Line


- Transports beam to the Booster
- Two dump lines located in the Linac vault, which provides opportunity to run just the Linac without injecting into the Booster tunnel.

Booster (3GeV)

- Accelerates electron beam from 200 MeV to 3 GeV
- Four Arcs, each equipped with nine magnet girders
- Four Straight sections (Injection, Extraction, Diagnostics & RF)

BtS Transport Line

- Transports beam to the Storage Ring
- One dump line located in the Booster tunnel, which provides opportunity to run just the Booster/Linac without injecting into the SR



Linac & Transport Lines

Installation Milestone

- Linac
- LBT-I
- LBT-II
- BST-I
- BST-II

Timeframe

Nov '11
Jan '12
Dec '12
Feb '13
Nov '13


24 Mo

Linac



Note: 24 months includes time to close Linac mis-steering event corrective actions (~ 1 year)

Transport Lines – (LBT & BST)



Booster Installation

Milestones

- Mechanical utilities installed
- First girder installed
- Last of 46 girders installed
- RF cavity installed and tested
- System integration
- Unit testing
- Integrated testing
- Supplemental Shielding
- PPS hardware installed

Completed

Mar '12

Feb '12

July '12

Jan '12

Jan '13

Mar '13

Mar '13

July '13

July '13

10 Mo
Accelerator
hardware



Total duration – Approximately 16 months



Injector Supplemental Shielding




**** Over 100 Supplemental Shields installed**

Storage Ring

- SR tunnel is comprised of five “Pentants” with each “Pentant” having six cells
- Each cell has one straight section and five Girders
- Straight sections will be occupied by IDs except at Injection and in two RF Cavity Straights (27 Straights will be available for IDs)
- Girders are equipped with magnets, vacuum components and advanced instrumentation



Double Bend Achromat Design



SR Girder/Magnet Installation

Dedicated Integration facility

- Assembly and Integration including vacuum chambers and some instrumentation.
- Magnet-magnet alignment ($< 30\mu\text{m}$)

Dedicated magnetic measurement lab

- Vibrating Wire
- Rotating Coil
- Hall probe

(150) Magnet Girders installed in tunnel

- Girder-girder alignment in tunnel ($< 100\mu\text{m}$)
 - 60 Dipoles
 - 300 Quadrupoles
 - 270 Sextupoles
 - 270 Correctors
 - 4 Bumps (Kickers)
 - 1 Injection Septum

Over 900 Magnets
Installed





Mechanical Utilities

- **14 Secondary Pump Skids**
 - 9 copper skids (Magnets, Absorbers, RF Transmitters, Booster Cavity, Beam Lines)
 - 5 aluminum skids (Vacuum chambers)
- **DI drops in SR tunnel**
 - Multipoles
 - Dipoles
 - Vacuum chambers
- **Process Chilled Water**
 - PCW cools racks located on tunnel mezzanine
- **AC power**
 - AC runs from “power centers” to racks
 - Cables pulled from racks through offset conduits (labyrinths) into SR tunnel






Storage Ring RF System

- **RF Transmitter (300KW)**
- **RF Cavity**
 - *Phase I commissioning* (mitigated SC Cavity delay)
 - 7 Cell Copper Cavity (Booster spare)
 - *Phase II Commissioning*
 - 500 MHz Superconducting RF Cavity is now installed and being used for commissioning at higher current
- **Cryo system**
 - Closed loop LHe system
 - LN2 system to provide pre-cooling
- **RF Blockhouse**
 - Used to test RF equipment prior to installation in the tunnel



Storage Ring Instrumentation

- (180) SR-RF BPMs
- (18) SR-ID BPMs
- (1) SR-XBPM
- (1) DCCT
- (1) SLM
- (5) Beam Loss Monitors
- Bunch-by-bunch feedback
- (1) Tune Monitor System
- (5) Scrapers - Horizontal/Vertical
- One Storage Ring Flag located in the Injection Straight
- Beam alignment Flags planned for all Front Ends (currently 6 installed)
- Dedicated X-Ray diagnostic beamline with a pin-hole camera
- Dedicated beamline with a 90° bend leading to SLM Hutch



Insertion Devices

Insertion Devices installed to date:

- (6) Damping Wigglers
 - (2) XPD
 - (4) Will be used on future beamlines
- (1) 1.5m IVU21 (SRX)
- (2) EPU's (CSX)
- (2) 3m IVU20 (HXN & CHX)
- (1) 3m IVU22 (IXS)





Time saving preparations:


- Tunnel floor prepared & cable trays installed in advance
- Rack installation & cable pulling is immediately performed after ID measurement are conducted
- ID specific vacuum chambers are installed just prior to ID installation (IVUs not included)

Front Ends

Six fully functional ID Front Ends installed to date: (XPD, SRX, CSX, HXN, CHX & IXS)





SR Supplemental Shielding



**** Over 250 Supplemental Shields installed**

Experimental Beamlines

Six beamlines now being commissioned
(XPD, SRX, CSX, HXN, CHX & IXS)



Readiness & Commissioning Achievements

Booster

- IRR
- ARR
- Commissioning

Completion Date

Sept 2013
Nov 2013
Feb 2014

Storage Ring

- IRR
- ARR
- Commissioning w/ 7 Cell Petra RF Cavity
- Commissioning w/ Superconductive RF Cavity

Jan 2014
Feb 2014
May 2014
Aug 2014

Beamlines & Operations

- IRR Group A (XPD & CSX Beamlines)
 - Commissioning of IDs & FE
- IRR Group B (HXN, SRX, IXS & CHX Beamlines)
 - Commissioning of IDs & FE

Aug 2014
OCT 2014

Oct 2014
Dec 2014 (expected)

NSLS-II Project Performance

Achieved excellent technical, cost & schedule performance

- Installation and commissioning milestones met on October 2014
- Cost Performance

	<u>Baseline</u>	<u>Actual</u>
Conventional Facilities	\$310M	\$311M
Accelerator Systems	\$295M	\$314M
Experimental Facilities	\$84M	\$93M
Pre-Ops	\$55M	\$56M
Project Management	\$68M	\$70M
R&D	<u>\$61M</u>	<u>\$61M</u>
-	\$873M	\$905M

- Baseline total with contingency = \$912M

Critical Path Activities

- SR & TL magnets (delivery and magnetic measurements)
- SR power supplies (installation)
- Pulsed magnets (design, fabrication and testing)
- Area Radiation Monitors – (delivery and testing)
- Supplemental Shielding (specification, design, fabrication & installation)
- Insertion Devices (delivery and magnetic measurements)
- Survey and Alignment (profiling of Girders in tunnel)
- SR RF Cavity (delivery & testing - mitigated by warm cavity)
- RF Cryo system (delivery and installation)
- PPS (software development, testing and certification)
- Readiness reviews (documentation for IRRs/ARRs)

Lessons Learned - General

- Bi-weekly meetings with “project controls” staff was essential
- Strong relationships between AD, PD and CF proved to be invaluable
- Importance of signage on barriers and methods of use
- Storage space considerations
 - Building delays required alternative storage solutions (secondary buildings, storage containers, cages on the experimental floor)
- Installation Coordination started well over a year before installation began
- Dedicated rigging teams are needed to affectively plan and schedule work
- A dedicated MRP system should have been obtained early on to facilitate efficient planning and control including:
 - Incoming receiving
 - Inventory control
 - BOM development for procurement and fabrication purposes.

Lessons Learned - Coordination


- “Installation Coordinator” reported directly to the Division Director
- Installation Coordination started well over a year before installation began
- Identified “Work Control Coordinators” for each group (enhanced planning of work and general safety)
- Wrote work plans prior to work starting (beware of scope creep)
- “Plan Of the Day” meetings held every morning on site
- Plan of the day information updated daily with activities & safety warnings
- Weekly installation coordination meetings for the Storage Ring and Injector were very effective
- Weekly “coordination walk-throughs” were scheduled to identify and resolve hardware conflicts
- Strong coordination with Conventional Facilities & Photon Division was essential
- Space limitations in the Injector complex required detailed planning & coordination
- Importance of barricades & signage

Lessons Learned - Labor

- Learning curves & setup was longer than expected, which led to slow ramp-up
- Installation “work profile” had a prolonged peak due to shifted work
- Time associated with preparing for IRRs & ARRAs was not planned
- Competition for survey/alignment resources
- Dedicated rigging team for project
- Underestimated labor for:
 - Shielding analysis & design
 - Electrical utilities & cable pulling
 - Mechanical utilities software effort
 - Rigging
- Resource leveling & schedule analysis performed to determine true schedule impact of delayed work & developed plans to mitigate
 - Additional temporary labor added to keep schedule on track
 - Some activities strategically shifted
- Schedule shifted from hardware driven to labor driven




Accelerator Installation Progress (percent complete)



Includes SR, Injector, PPS & Insertion Device Installation WBSs

Accelerator Installation Work Profile (FTEs)



Includes: SR, Injector, PPS & Insertion Device Installation WBSs

Challenges Experienced


- Delayed “beneficial occupancy” of ring building made planning difficult
- Extensive punch-list after receiving beneficial occupancy
- Coordinating multiple activities & teams during installation
- Coordination to avoid interferences between systems (walk-downs required)
- Difficulties associated with performing installation, integrated testing and commissioning in parallel

example: Access to Pentants 1 & 2 limited during Booster commissioning

- There were limitations associated with having only one ID measurement lab
- SR Supplemental Shielding design, construction and documentation (> 350 Shields)
- Shortage of specialized installation labor
- Component delays (i.e. magnets, RF cavity, etc.) required additional planning to balance activities and resources.
- Limited floor space for staging materials and performing secondary installation activities
- Transportation of material during & after Hutch installation is often difficult

NSLS-II Project Success

- 3 GeV Accelerator has been commissioned up to 50mA
(project milestone achieved – reaching higher currents over this next year)
- Commissioning of six Insertion Device “project” beamlines underway
- CD 4 planned for February 2015
- Construction of additional beamlines already underway



Proper planning and coordination are the keys to success.